

EVBox Troniq Products

Product Type Guide

DC 18 - A B C - D E F - G H I

STATION	MODEL	CABLE (RIGHT SIDE)	CABLE (LEFT SIDE)	AC	POWER MODULES/ OUTPUT	SENSORS	EMV PAYMENT	DC METER	REGIONAL COMPLIANCE	PRODUCT LINE
DC: DC Charger	18: Troniq	<p>2: CCS2 dry 500 A / 250 A long</p> <p>3: CCS2 cooled (modular)</p> <p>4: CCS2 dry 500 A / 250 A (Compact)</p> <p>7: CCS2 dry 500 A / 375 A short</p> <p>8: CCS2 dry 500 A / 375 A long</p> <p>9: CCS2 cooled short</p> <p>A: CCS2 cooled long</p> <p>B: CCS1 dry 350 A short</p> <p>C: CCS1 dry 350 A long</p> <p>D: CCS1 cooled short</p> <p>E: CCS1 cooled long</p> <p>F: CCS2 500A / 375A extra long (EAP)</p> <p>G: NACS dry short</p> <p>H: NACS dry long</p> <p>J: CCS2 dry 500 A / 250 A short</p> <p>L: NACS cooled short</p> <p>M: NACS cooled long</p>	<p>2: CCS2 dry 500 A / 250 A long</p> <p>3: CCS2 cooled (modular)</p> <p>4: CCS2 dry 500 A / 250 A (Compact)</p> <p>5: CHAdeMo 125 A (Compact)</p> <p>7: CCS2 dry 500 A / 375 A short</p> <p>8: CCS2 dry 500 A / 375 A long</p> <p>9: CCS2 cooled short</p> <p>A: CCS2 cooled long</p> <p>B: CCS1 dry 350 A short</p> <p>C: CCS1 dry 350 A long</p> <p>D: CCS1 cooled short</p> <p>E: CCS1 cooled long</p> <p>F: CCS2 500A / 375A extra long (EAP)</p> <p>G: NACS dry short</p> <p>H: NACS dry long</p> <p>J: CCS2 dry 500 A / 250 A short</p> <p>K: CHAdeMO 125 A short</p> <p>L: NACS cooled short</p> <p>M: NACS cooled long</p>	<p>1: No AC socket</p> <p>2: AC socket (with AC MID meter)</p>	<p>3: 3 X 30 KW = 90 KW</p> <p>4: 4 X 30 KW = 120 KW</p> <p>5: 5 X 30 KW = 150 KW</p> <p>6: 6 X 30 KW = 180 KW</p> <p>7: 7 X 30 KW = 210 KW</p> <p>8: 8 X 30 KW = 240 KW</p> <p>H: 8 x 40kW = 320kW</p> <p>I: 9 x 40kW = 360kW</p> <p>J: 10 x 40kW = 400kW</p> <p>K: 11 x 40 kW = 440 kW</p> <p>L: 12 x 40 kW = 480 kW</p> <p>B: 2 x 40 kW = 80 kW (demo)</p>	<p>1: No sensor</p> <p>2: Tilt and door switch</p> <p>3: Tilt switch</p> <p>4: Door switch</p>	<p>1: Not included</p> <p>2: Payter P66</p> <p>3: Payter P68</p> <p>4: Payter Apollo</p> <p>5: Payter Apollo Polar</p> <p>6: Castles U1F</p> <p>7: Castles SIU2</p> <p>8: Worldline Valina</p> <p>9: CPI Alio Pro</p>	<p>1: Uncertified DC meter</p> <p>3: 2 x Eichrecht certified DC meters</p> <p>5: 2 x MID / LNE certified DC meters</p> <p>6: 2 x CTEP certified DC meters</p>	<p>1: CE</p> <p>2: UL</p>	<p>1: Modular Standard Height</p> <p>2: Modular Compact Height</p> <p>3: High Power</p> <p>4: High Power 480 kW (EAP)</p> <p>5: Modular Standard Height Generation 1+ (Remote Diagnostics Board)</p> <p>6: Modular Standard Height Generation 2</p>